विनयलता एस. Vinayalatha S. कुलसचिव Registrar



गणितीय विज्ञान संस्थान THE INSTITUTE OF MATHEMATICAL SCIENCES (परमाणु ऊर्जा विभाग, भारत सरकार का एक स्वायत्त संस्थान)

(An Autonomous Institution under Dept. of Atomic Energy, Govt of India)
CIT CAMPUS, TARAMANI, CHENNAI - 600113



फोन/Phone: 044-22543150 & 044-22541416 (Direct), 044-22543100/166(Board) वेबसाइट/Website : www.imsc.res.in फ़ैक्स/Fax : 044-22541586 (general) ईमेल/Email: registrar@imsc.res.in

Ref: SCRAP YARD ELECTRICAL WORK/IMSc/2025

21.07.2025

22

To:

Sir.

Kindly send your competitive rates for providing lights, wiring, and providing fan points supply, switches, sockets, and switch boxes in the scrap yard at Guest House campus. You are requested to inspect scrap yard at Guest House campus and send your sealed quotations to reach us on or before 31.07.2025 at 15.00 Hrs. The Institute reserves the right to reject any or all the quotations or to allot parts of the work to different agencies without assigning any reason. For any clarification contact our phone no: 044- 22543149.

REGISTRAR

Tenders are advised to take note of the following points into consideration while quoting

- 1. E mail / fax quotation will not bre accepted.
- 2. The rates are inclusive of all taxes, labour charges and materials etc. nothing will be paid extra.
- 3. Scheduled contract peroid is 2 months.
- 4. The payment shall be made after completion of the work and as per the actual measurement at site.
- 5. Late quotation will not be considered.
- 6. Tenderes are requested to quote their rates after site inspection and as per the scope of works.

Enclosed: Blank schedule.

Name of work: Providing lights, wiring and allied work in scrap yard shed at Guest House campus at IMSc, Taramani – Reg.

The rate quoted shall be inclusive of GST and IMSc will not entertain any claim whatsoever in this respect.

| Sl. No. | Description of Item | Unit | Qty | Rate in Rs. | Amount in Rs. |
|------------|--|------|-----|-------------|---------------|
| 1 | Supply and fixing of 8way SPN DD MCB DB with following incoming and outgoing MCB as required. Make: Legrand, Havells, L&T. | | | | |
| | Incoming: 32Amps DP MCB – 1No Outgoing: 6Amps SP MCB – 6Nos | Set | 1 | | |
| 2 | Supply, laying of 3C x 2.5 sq mm Copper Armoured cables from OGH Power panel to SPN DB as directed by engineer-incharge. Make: Polycap,KEI,Finolex. | mt . | 40 | | |
| 3 | Supply and making end termination of 3core 2.5sq.mm copper cable in a suitable cable gland and crimping socket etc as required. | no | 2 | | |
| 4 | Supply and laying of following size FRLS copper wires in existing PVC conduits with necessary end terminations and earthings in wall / ceiling with necessary supports / clamps and screws etc. for site condition and as directed by engineer-in-charge. Make: Polycap,KEI,Finolex. | | | | |
| a) | 2 x 2.5 sqmm + 1 x 1.5 sqmm CU FRLS wires | mt | 25 | | |
| b) | 3 x 1.5 sqmm CU FRLS wires for point wiring. | mt | 90 | | |
| 5 | Supply and laying of following size PVC conduits / Casing capping for various wirings, accessories like bend, junction boxes, elbow and tee etc. and completion of work as directed by engineer-in-charge suitable for open wiring as required with neat workman ship. Make: Vasavi, Finolex, Polycap. | | , | | |
| a) | 25 mm dia Heavy duty PVC pipe | mt | 9 | | |
| b) | 19 mm dia Heavy duty PVC pipe | mt | 40 | | |
| 6 | Supply and fixing of approved make modular type metalic boxes, switches, sockets, Step type Fan regulators, base plates, cover-plates, dummy plate etc. as directed by engineer in charge. Make: Crabtree, MK, Legrand. | | | | |
| a) | 6 / 10 A one way Switch | no | 12 | | |
| b) | 16A one way switch with indicator. | no | 1 | | |
| c) | 6 / 10 A 5 pin Shuttered socket universal type | no | 4 | | |
| d) | 16 A 5Pin shuttered socket | no | 1 | | |
| e) | One module dummy | no | 4 | | |
| | MODULAR METAL BOX (GI box 1.2 MM thickness) | | | | |
| f) | 2/3 module modular metal box | no | 2 | | |

| | | no | 1 | | |
|------|---|----|------|----------|---------------------------------------|
| g) | 6 module modular metal box | | | | * * * * * * * * * * * * * * * * * * * |
| h) | 8 module modular metal box | no | 2 | | |
| | MODULAR BASE PLATES AND FRONT PLATES | | | | <u> </u> |
| I) | 2 / 3 module base plate and cover plate | no | 2 | | |
| | 6 module base plate and cover plate | no | 1 | | |
| k) | 8 module base plate and cover plate | no | 2 | | |
| 7 | Supply and fixing of 20watts wall mounted box type LED light fitting with LED light ,Make : Philips,Crompton,Bajaj. | no | 8 | | |
| 8 | Supply and fixing of 20watts led Bulk head fittingt, Make: Philips, Crompton, Bajaj. | no | 4 | | |
| 9 | Supply and fixing of 200wats,IP 65 led flood light fitting and fixing accessories as required. Make: Philips,Crompton,Bonsai. | no | 2 | | |
| 10 | Supply and fixing of 20watts led garden light fitting with its complete set etc., as required suitable for the site condition and directed by engineer-in-charge. Make: Philips, Crompton, Bajaj. | 1 | 4 | | |
| 11 | Supply and fixing of 1200MM high speed ceiling fan with its complete set etc., as required suitable for the site condition and directed by engineer-in-charge. Make: Crompton, Bajaj, Usha. | No | 3 | | : |
| | | | Tota | l in Rs. | |

| | <i>'</i> |
|---------------------|----------|
| | I |
| (Rupees in words | |
| I KIIDEES III WULUS | |

Signature of vendor / contractor with seal and address)