विनयलता एस. VINAYALATHA S. कुलसचिव REGISTRAR

गणितीय विज्ञान संस्थान THE INSTITUTE OF MATHEMATICAL SCIENCES

(परमाणु ऊर्जा विभाग, भारत सरकार का एक स्वायत्त संस्थान)



(An Autonomous Institution under Dept. of Atomic Energy, Govt of India) CIT CAMPUS, TARAMANI, CHENNAI - 600113

फोन/Phone: 044-22543150 & 044-22541416 (Direct), 044-22543100/166(Board)

फ़ैक्स/Fax : 044-22541586 (general)

वेबसाइट/Website : www.imsc.res.in

ईमेल/Email: registrar@imsc.res.in

Ref: IMSc / Civil / QUT /06-2024

06.03.2024

To

Sub: Providing tiles flooring in the Godavari flats in the Guesthouse campus, IMSc at Taramani. - Inviting sealed quotation - Reg.

Sir/Madam,

Sealed Quotations are invited by the Registrar, IMSc, Taramani on behalf of the Director, IMSc for "Providing tiles flooring in the Godavari flats in the Guesthouse campus, IMSc at Taramani." You are requested to fill up the same and sent to us so as to reach on or before 15.03.2024 at 1500 hrs at the Main building, IMSc, in a sealed cover superscribing the quotation no. The Institute reserves the right to reject any or all the quotations or to allot parts of the work to different agencies without assigning any reason.

For and on behalf of the Director, IMSc

Tenderers are advised to take note of the following points into consideration while quoting

- 1. E mail/ fax quotations will not be accepted.
- 2. The rates are inclusive of all taxes, labour charges and materials etc. nothing will be paid extra.
- 3. The period is to be 10 days.
- 4. The payment shall be made after completion of the work and as per the actual measurement at site.
- 5. Late quotations will not be considered.

Enclosed: Blank Schedule.

THE INSTITUTE OF MATHEMATICAL SCIENCES

C.I.T CAMPUS, TARAMANI

Name of Work: Providing tiles flooring in the Godavari flats in the Guesthouse campus, IMSc at Taramani.

Note: The rates quoted by the tenderer in the schedule shall be inclusive of Goods and Service Tax (GST) of 18% or any other Tax applicable. GST or any other tax applicable in respect of this contract shall be payable by the Contractor and Government will not entertain any claim whatsoever in respect of the same.

	Schedule of Quantities					
S. No	Description of Item	Qty	Unit	Rate in Rs. P	Amount in Rs. P	
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead etc and as per the specifications and as directed by the Engineer in charge. (a) For thickness of Mosaic/tiles with cement mortor above 25 mm and up to 50 mm	18.00	Sqm			
2	Providing cement mortar 1:4 (1 cement: 4 coarse sand) for leveling the undulated floor area and making a bed for the tiles flooring base which required extra thickness of mortar beyond the tiles flooring item cement mortar thickness and as directed by the Engineer- in-charge.	1.00	Cum			
3	Providing and laying full body Vitrified tiles Matt/Antiskid finish in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily cleaning the surface, etc., all complete as per manufacturer's specification and as directed by Engineer- in-charge. Note: The sample Tile got approved by the Engineer in charge before procurement. Size of Tile 600 x1200 mm with wooden pattern or other required pattern.	82.00	Sqm			

C No Decembries of Items (1977 1971)	Amount in Rs. P			Schedule of Quantities						
different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc. Complete. (a) Size of Tile 600 x1200 mm with wooden pattern or other required pattern. Hacking of cement concrete floor/mosaic flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge. Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. Providing and applying wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and			Unit	Qty	Description of Item	S. No				
Hacking of cement concrete floor/mosaic flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge. Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. Providing and applying wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and			Sqm	9.00	different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in <u>skirting</u> , riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc. Complete. (a) Size of Tile 600 x1200 mm with wooden pattern or	4				
raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. Providing and applying wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and			Sqm	85.00	Hacking of cement concrete floor/mosaic flooring including cleaning for surface etc. complete as per direction of the Engineer-in-	5				
with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and			Sqm	9.00	raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground	6				
			Sqm-	132.00	with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and	7				
Total Amount in Rs.		nount in Rs.	Total An							
upees in words:		l			in words:	upees i				
gnature of the Tenderer :										