



Ref: IMSc / 2 TR Casette AC / 2026-27

Date: 24.07.2026

To :

Sir,

Kindly send your competitive Quote / rate for the Supply, Installation, Testing and Commissioning of 2 TR Casette AC and 1 TR Split AC, which is to be installed in Admin building at IMSc campus. The Contractors / Vendors those who have interested to participate in this tender, kindly inspect IMSc site and send your **sealed quotations** to reach us **on or before 04.08.2026**. The Institute reserves the rights to reject any or all the quotations or to award the purchase order to different vendors without assigning any reason. For any further clarifications, please contact Scientific Officer (Electrical), IMSc and our phone no. 044 - 22543300 /149.

Sl.No	Description	Unit	Qty	Supply Rate in Rs.	Erection Rate in Rs.	Total Rate in Rs.	Amount in Rs.
1.	SITC of 2 TR capacity Inverter model Air cooled Cassette type AC unit with 3/4 star ratings (Blue star make, Model No. CIA324TXU1PS) with Indoor unit (IDU), Out door unit (ODU) of copper coils, R-32/R410A/R-407 Green Refrigerant, wireless Remote, inbuilt drain pump, suitable for 230V, 50 Hz ,1 phase AC supply, including surface / concealed copper Refrigerant piping with insulation (closed cell elastomeric nitrile rubber tubular pipe section) upto 5.5 Mtr (IDU to ODU), copper power and control cable upto 5.5 Mtr (IDU to ODU) including CPVC drain pipe outdoor stand and core cutting of wall, the system shall be capable of performing cooling, dehumidification, Air circulation, filtration & ventilation of Scroll/rotary compressor with min 5 year Original Equipment Manufacturer (OEM) warranty both compressor and Printed Circuit Board (PCB) as specified and suitable for the site conditions in the existing gypsam board false ceiling as directed by Engineer in charge. Make: Blue star make, Model No. CIA324TXU1PS	Set	1				

2.	SITC of 1 TR capacity Inverter model Air cooled Hi wall Split type AC unit with 3/4 star BEE ratings complete with Indoor unit (IDU) and Outdoor unit (ODU) of copper coils, surface / concealed copper Refrigerant piping with insulation (closed cell elastomeric nitrile rubber tubular pipe section) upto 3 Mtr (IDU to ODU), copper power cable upto 3.5 Mtr (IDU to ODU) including CPVC drain pipe, R-32/R-410/R-407 Green Refrigerant, wireless Remote control, outdoor stand, core cutting of wall suitable for working between 180- 260V with low & high voltage cutoff and 50 hz ,1 phase AC supply capable of performing cooling, dehumidification, air circulation with Scroll / rotary compressor. Min 5 year Original Equipment Manufacturer (OEM) warranty both compressor and Printed Circuit Board (PCB). Make: Blue star/ Voltas/Hitachi/ Diakin/ O General	Set	1				
3.	Supply and fixing of additional copper pipe between indoor and outdoor copper coils (if required) as directed by Engineer in charge	Mtr	8				
4	Supply and fixing of 16Amps plug top suitable for AC socket.	No	2				
TOTAL AMOUNT IN Rs.							

(Rupees in words _____)

Note: Tenderer are advised to consider following points into consideration while quoting their rates:

1. E – mail / fax quotations will not be accepted.
2. The completion period shall be **within 7 Days**.
3. The payment will be made against the satisfactory completion and acceptance of the work.
4. Late quotations will not be considered.
5. Contractors / Vendors/ OEM are requested to quote their rates after site inspection and as per the scope of work.
6. The quoted rates shall be inclusive of GST and any other taxes and IMSc will not entertain any additional claim whatsoever in this regard.

Vinayalatha S.

REGISTRAR

Signature of the Vendor / Contractor
with seal and address